

Shell Eco-marathon

Midpoint Presentation

March 4, 2014

Abdul Alshodokhi, Moneer Al-Jawad, Jericho Alves, John Gamble, Nikolaus Glassy, Benjamin Kurtz, Travis Moore

Overview

- Project Background
- Frame Status
- Drivetrain Status
- Engine & Fuel Status
- Electrical Status
- Steering & Braking Status
- Project Updates/Changes
- Project Timeline
- Conclusion

Project Background

Design a vehicle that maximizes fuel efficiency for the Shell Eco-marathon competition

Competition Information

- Competition hosted by Shell
- Capstone project representing SAE NAU

Technical Advisor

- Dr. Tester



Frame Status

The skeleton of the frame has been completed, but the following issues are limiting the team from full completion:

- Fabrication and install of rear wheel dropouts
- Fabrication and install of front wheel steering mounts
- Fabrication and install of motor mounts
- Fabrication and install of intermediary drive shaft mounts
- Fabrication and install of frame floor



Frame Status

Frame Skeleton Progress: CAD design to current fabrication status



Frame Status

Frame Skeleton Progress: CAD design to current fabrication status





Drivetrain Status

The drivetrain has been fully designed, but the following issues are limiting the team from full completion:

- Intermediary drive shaft bearings need to be ordered and installed
- Sprocket gear skeletonization (i.e. remove excess material/weight)
- Install rear sprocket onto rear hub
- Design, fabrication, and install of chain guard
- Install all drivetrain components

Drivetrain Status

Drivetrain Progress: CAD design to current fabrication status




Engine & Fuel System Status

The engine and fuel system has been fully designed and mostly completed. The following issues are limiting the team from full completion:

- 80% engine tune completion
- New exhaust pipe design (vent outside vehicle)
- Possibility of acrylic pressure vessel
- Install all engine and fuel related components in final locations on the vehicle



Engine Status

Engine Progress: Original to current fabrication status




Engine Status

Engine Progress: Original to current fabrication status




Engine Status

Engine Progress: EcoTrons User Interface for tuning




Engine Status

Engine Progress: Continuous Sample Parameter Plot




Engine Status

Engine Progress: 100ms Parameter Plot





Engine Status

Engine Progress: 20ms Parameter Plot



Fuel System Status

Fuel System Progress: Fuel schematic to current fabrication status




Electrical System Status

The electrical system has been fully designed and mostly completed. The following issues are limiting the team from full completion:

- Integrating the horn, external safety switch, starter light, and additional driver accessories
- Re-wiring the electrical system once all components are mounted in final locations

Electrical System Status

Electrical System Progress: Electrical schematic to current fabrication status





Steering & Braking Status

The steering has been fully designed. The following tasks are necessary in order for full completion:

- Fabricate and install steering uprights
- Fabricate and install steering column
- Install front and rear wheels
- Install front and rear brakes


Steering & Braking Status

Steering Progress: CAD design to current fabrication status



Steering & Braking Status

Steering Progress: CAD design to current fabrication status



Project Update/Changes

Due to certain circumstances, the team had to make the following changes to the project:

- Fairing construction delayed 1/31 to 4/24
- Functioning vehicle delayed to 3/25
- Frame skeleton delayed to 3/4
- Prototype testing start 3/25 to 4/20
- Electrical system delayed to 4/6

Project Timeline



Conclusion

- The team has completed about 40% of the vehicle fabrication and install process.
- The team has documented each sub-system with CAD files and pictures of the fabrication and install processes.
- The team will have a rolling chassis by 3/14.
- The team will have a functioning vehicle and begin final prototype testing by 3/25.
- The engine and fuel tuning is at 80% completion.
- The team's new estimate of the average fuel economy is 650 mpg based on a conservative estimate with cycling the motor.

Questions?